

Ameren Illinois is replacing and upgrading an existing 230 kV transmission line and associated facilities from Cahokia to Joppa.

The existing line was originally built in the 1950's, and will be replaced and upgraded to a 345 kV line to better align with Ameren Illinois' current energy system and to create additional customer benefits. Replacing the aging infrastructure and upgrading this transmission line will improve energy reliability, promote access to renewable energy like solar, and increase transmission capacity. Construction will occur in six project segments along the existing transmission corridor.

Existing Structures

230 kV

Wood H-frame

Avg. Height 65 ft

Avg. Span Length

650 ft

Structures/mile

Conductor Clearance

23 ft

Direct embed

Typical Structures

345 kV

Steel H-frame

Avg. Height

80 ft

Avg. Span Length

800 ft

Structures/mile

6-7

Conductor Clearance

25 ft

Crushed Rock Direct Embed

Project Benefits



Replacing aging infrastructure and upgrading our energy system to improve reliability



Promoting access to renewable energy sources like solar



Increasing transmission capacity

150 ft easement

approximately 22 ft

Segment 6: Jordan to Joppa



Construction Activities & What to Expect

ROW & Field Surveys



Spring - Fall 2020

Soil borings and environmental and cultural field surveys help to identify pole locations, historical and archaeological resources, wildlife habitat, native prairie, wetlands and streams.

Pre-Construction



Spring - Summer 2022

Prior to construction, crews will clear the right-of-way of debris, and vegetation.

Pole locations will be flagged for construction.

Materials will be staged in areas along the route.



Fall 2022 - Spring 2023

During construction, crews will dig holes, set and place poles and string wires

You may notice large equipmen working along roadways and along roadways and along our right-of-way.

Restoration



Spring 2023

Once construction is nearly complete, crews will clean up project work areas and begin restoration of the right-of-way, access roads and material yards.







